

4.12 Temporary Standpipes in Buildings under Construction (2019)

Reference: 2019 San Francisco Fire Code (SFFC), Sections 905.3.1 & 3313

Purpose: The following requirements are provided for the fire inspector's information and to assist contractors during construction.

- I. At least one standpipe shall be provided in every building under construction that is required to have standpipe(s) per SFFC Sec. 905.3.1 (or required by SFFD). Such standpipes shall be installed when the building has reached a height of not more than 40 feet in height above the lowest level of Fire Department vehicle access or greater than 150' travel distance. **Fire department connections (FDC) and standpipe outlet valves shall comply with the requirements of SFFD Administrative Bulletins 4.05, 4.06 & 4.24.**

- II. The following additional stipulations shall apply to buildings which will exceed 200 feet in height:
 - A. Submit detailed plans for approval to the Fire Marshal, Division of Fire Prevention and Investigation;
 - B. When building reaches 200-ft. elevation, a fire pump shall be in operation with power and water provided; controls shall be at ground floor.
 - C. Provide signs and necessary keys to gain access and operate equipment.
 - D. Domestic and construction water connections may not be taken off the standpipe system.
 - E. If a UL labeled and listed pump is not available, a dependable equivalent may be accepted for temporary use, if approved by SFFD.
 - F. Maximum static pressure at any Fire Department outlet shall be 175 psi or approved PRVs shall be installed.
 - G. The sizing of the pump shall be based on sound engineering principles and approved by the SFFD.

GENERAL NOTE: Any part of the permanent standpipe may be used on a temporary basis, with the approval of the fire code official.